

Harrison
 H
 6-11-75
 2905
 6/11/75
 date well completed 19

MISSISSIPPI
 BOARD OF WATER COMMISSIONERS
 416 North State Street
 Jackson, Mississippi 39201

~~CODED~~

WATER WELL DRILLERS LOG

COASTAL DRILLING & SERVICE CO. Harrison

ROUTE # 1 BOX 618

county well located

LANDOWNER: PT. Brady BILOXI MISS. 39522

Pt 2 Box 792 E
Brady, Miss
 (mailing address)

WELL LOCATION: 135

sec 23 T 6 N R 10 E
(3) Three miles NW of Cedar Lake
 (distance) (direction) (nearest town)

WELL PURPOSE: Home
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 2"
- (2) total depth (feet) 725'
- (3) static water level (feet) 32 below above top of ground.
- (4) casing PVC 710'
 (material) (depth)
 (size) if telescope see back.
- (5) screen 15' 710'
 (length) (depth to top)
1" PVC
 (size) (material)
- (6) pump One 12
 (HP) (yield gpm)
Ele
 (type power)
- (7) electric log No
 (yes or no)
 (organization running log)

description of formations encountered	from	to
Top Soil	1	3
Red Clay Sand	3	3.5
White claus	3.5	60
Red Sand	60	85
Blue Soft Clay	85	160
White Sand	160	200
hard Blue Clay	200	310
fine water sand	310	345
hard Blue Clay	345	480
fine water sand	480	525
dry hard clay	525	660
Rock	660	665
fine water sand	665	680
fine water sand	680	725


(8) how well bottom plugged
2nd hand watch block

DRILLERS REMARKS:

RECEIVED
 JUL 17 1975

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.