

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

WATER WELL DRILLERS LOG

Harrison
H
2308

9-18-85

date well completed

Coast Water Well Harrison

firm name

county well located

LANDOWNER: Minnie Fuller

Hwy 15

Biloxi, Ms

(mailing address)

WELL LOCATION:

sec 18 T 6 N R 9 E
S W
7 miles NW of D'IBERVILLE
(distance) (direction) (nearest town)

WELL PURPOSE: home
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 2"

(2) total depth (feet) 325'

(3) static water level (feet) 65' below above top of ground.

(4) casing PVC, 310'
(material) (depth)
2"
(size) If telescope see back.

(5) screen 10', 310'
(length) (depth to top)

2", PVC
(size) (material)

(6) pump _____ (HP) _____ (yield gpm)

_____ (type power)


(7) electric log no
(yes or no)

_____ (organization running log)

(8) how well bottom plugged backwash valve

DRILLERS REMARKS:
5'-2" tail pipe

Description of formations encountered	from	to
<u>Top Soil</u>	<u>0'</u>	<u>5'</u>
<u>Gray Coarse Sand</u>	<u>5'</u>	<u>90'</u>
<u>Pea Gravel</u>	<u>90'</u>	<u>120'</u>
<u>Blue Clay</u>	<u>120'</u>	<u>295'</u>
<u>Gray Coarse Sand</u>	<u>295'</u>	<u>320'</u>
<u>Blue Clay</u>	<u>320'</u>	<u>325'</u>



Department of Natural Resources
Bureau of Land & Water Resources

