

HAR.

## MISSISSIPPI BOARD OF WATER COMMISSIONERS

L 44

11-14-62

## WATER WELL DRILLERS LOG

L  
CODEDDate: Nov. 14, 1962, Driller: M & B Drilling Co County Attala  
(Name)(1) Owner of Land: Carroll Williams  
(Name)Three Rivers Rd. Outpost, Miss  
(Address)(2) Location: SE 1/4, 1E 1/4, Sec. 3 T28N14W5 miles N of Outpost  
(distance) (direction) (Nearest Town)(3) Topography: Flat  
(Hilly) (Flat) (Level)(4) Purpose of Well: Domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)Description & Color of Materials  
Sand, Clay, Red Clay, Shell, etc.Thick-  
ness  
FeetDepth  
Feet

Clay	9	9
White Sand	11	20
Yellow Clay	4	24
Black Muck Clay	11	35
Yellow Clay	7	42
Blue Clay	20	62
Fine Grey Sand	8	70
Blue Clay	172	242
Fine Sand	6	248
Blue + Yellow Clay	82	330
Grey Sand	22	352

Information upon completion of well:

Top 70 FT 2", Balance 1 1/4"

(1) Diameter \_\_\_\_\_ inches.

(2) Total Depth 350 feet.(3) Water Level 27 feet below top of ground.(4) Cased to 345, Size 2" X 1 1/4"(5) Screen: Size 2" X 80/100, Length 5 FT.

(6) Were any formations sealed against pollution?


\_\_\_\_\_ yes, \_\_\_\_\_ no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: \_\_\_\_\_

CODED



Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss

1890

1890