

Harrison
L177
2-67

MISSISSIPPI BOARD OF WATER COMMISSIONERS

CODED

WATER WELL DRILLERS LOG

Date: Feb. 24, 1967, Driller: M & B Drilling Co. County Harrison
(When well drilled) (Name) (Where well is located)

1) Owner of Land: Fred Rose
(Name)
Subpart
Old. Highway 49, New Highway 49
(Address)
 2) Location: SW 1/4, SE 1/4, Sec. 28 T8 R11W
North City Limits - 1/2 mile
(distance) (direction) (Nearest Town)
 3) Topography: Flat
(Hilly) (Flat) (Level)
 4) Purpose of Well: Domestic
(Domestic Irrigation Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Fill	2	2
Swamp	4	6
Sand	10	16
Dark Grey Clay	6	22
Sand	6	28
Light Grey Clay	22	50
Sand	10	60
Black Organic Mottled Light Grey Clay	20	80
Blue Clay	25	105
Sand Break	10	115
Blue Clay	25	140
Fine Powder Sand	15	155
Blue Clay	80	235
Coarse Grey Sand	35	270

Information upon completion of well:

Plastic
 1) Diameter 2 inches.
 2) Total Depth 270 feet.
 3) Water Level 7 feet below top of ground.
 4) Cased to 270, Size 2"
Crown Plastic #10 slot
 5) Screen: Size 2", Length 6 FT

STILL cutting Coarse sand at bottom of hole

CODED

6) Were any formations sealed against pollution?
 _____ yes, _____ no.

YES depth of formation _____


by _____

Drillers Remarks: _____

Yield in gpm: _____

Size pump: 1/2 HP - 13 gallon Stokes Well

Type power: 110 Volt 1Ø



COPIED

