

Harrison
 L310
 1-67

MISSISSIPPI
 BOARD OF WATER COMMISSIONERS
 416 North State Street
 Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

1-20 1967 SUTTER Well Works HARRISON
 date well completed firm name county well located

LANDOWNER: J.K. MILNER
 Coca Cola Bottling Co.
 GULFPORT, Miss.
 (mailing address)

WELL LOCATION: 29711
 sec _____ T _____ N R _____ E
 Just west of Hwy 49 W
 _____ miles _____ IN of GULFPORT
 (distance) (direction) (nearest town)

WELL PURPOSE: INDUSTRIAL
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:


- (1) diameter (inches) 6
- (2) total depth (feet) 1178
- (3) static water level (feet) 9 below above top of ground
- (4) casing BLACK, 1148,
 (material) (depth)
6"
 (size) If telescope see back.
- (5) screen 30, 1148'
 (length) (depth to top)
6", STAINLESS STEEL
 (size) (material)
- (6) pump 10 100
 (HP) (yield gpm)
- ELEC.
 (type power)
- (7) electric log No
 (yes or no)
- _____
 (organization running log)

(8) how well bottom plugged B.P. VALVE

DRILLERS REMARKS:

description of formations encountered	depth	
	from	to
Clay	0	240
sand	240	265
Clay	265	627
sand	627	650
Clay	650	801
fine sand	801	825
Clay	825	890
sand	890	912
Clay	912	1107
sand	1107	1178

CODED



If well telescopes please sketch and show depths.

GROUND LEVEL

SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.

MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY
 Office of Land and Water Resources
 P. O. Box 2309
 Jackson, MS 39225
 Water Well Plugging/Decommissioning Form
 OLWR-DF-1 (04/08)

RECEIVED
DEC 04 2018
BY OLWR

COUNTY WELL LOCATED: <u>Harrison</u>		WELL NUMBER: <u>047L310</u>	
PERMIT NUMBER: <u>N4 GW-1042</u>		DATE WELL PLUGGED: <u>11/27/2018</u>	
NAME OF FIRM PLUGGING WELL: <u>Lyman Well</u>		TELEPHONE NUMBER: <u>228-832-3193</u>	
NAME AND ADDRESS OF CURRENT LANDOWNER: <u>Coca-Cola United</u> <u>3701 25th Ave Gulfport MS 39503</u>			
WELL LOCATION: SECTION: <u>29</u>		TOWNSHIP: <u>75</u> RANGE: <u>11W</u>	
WELL LOCATION: LATITUDE: <u>30 23 43 N</u>		LONGITUDE: <u>089 05 42 W</u> METHOD (CIRCLE ONE): <input checked="" type="checkbox"/> (1) USGS QUAD <input type="checkbox"/> (2) CONVENTIONAL SURVEY <input type="checkbox"/> (3) GPS - HAND HELD OR SURVEY GRADE	
DISTANCE: _____ DIRECTION: _____		NEAREST TOWN: _____ OTHER LANDMARK: _____	
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL, ETC.): <u>Industrial</u>			
NAME OF WELL CONTRACTOR WHO DRILLED THE WELL: <u>Coca Cola Bottling Sutter</u>			
NAME OF LANDOWNER WHEN WELL WAS DRILLED: <u>J.K. Miller</u>			

WELL DATA			
WELL DEPTH: <u>1178'</u>		HOLE DEPTH: <u>1178</u>	
CASING DIAMETER (IN.): <u>6</u>	CASING LENGTH (FT.): <u>1148'</u>	TYPE OF CASING: <u>galvanized</u>	
DEPTH TO STATIC WATER LEVEL: <u>30'</u>		DATE WELL COMPLETED: <u>1-67</u>	
WHY IS THE WELL BEING ABANDONED? <u>Not in use</u>			

DESCRIBE HOW THE WELL OR HOLE WAS PLUGGED (AMOUNT OF CASING AND/OR SCREEN THAT WAS REMOVED OR LEFT IN HOLE, MATERIAL AND AMOUNT USED IN PLUGGING, METHOD OF PLACING MATERIAL, ETC.)

The well was perforated @ a depth of 300'. A tremmie pipe was ran + 230 cuft. of neat cement was pumped back to the surface

I CERTIFY THAT THE WELL WAS PLUGGED OR ABANDONED IN ACCORDANCE WITH THE STATE OF MISSISSIPPI REGULATIONS.

Josh Kadner 0-640
 PRINT NAME MS LICENSE NUMBER

[Signature] 11/28/18
 SIGNATURE DATE