

HAR.  
L  
3-62

### WATER WELL DRILLERS LOG

14

Date: Mar, 1962, Driller: Joe Miller County Harrison  
(Name)

(1) Owner of Land: Joe Miller  
(Name)  
Cliffport Miss  
(Address)

(2) Location:         $\frac{1}{4}$ ,         $\frac{1}{4}$ , Sec.        T.        R.         
       miles of         
(distance) (direction) (Nearest Town)

(3) Topography: Flat  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Surf. Clay</u>		<u>8'</u>
<u>Wh Sand</u>	<u>6'</u>	<u>14</u>
<u>Blue Clay</u>	<u>26'</u>	<u>40</u>
<u>White Clay</u>	<u>86'</u>	<u>126</u>
<u>Blue Clay</u>	<u>256'</u>	<u>382</u>
<u>Thin (Blue) Sand</u>	<u>20'</u>	<u>402</u>
<u>Blue Clay</u>	<u>88'</u>	<u>490</u>
<u>Light Blue Clay</u>	<u>95'</u>	<u>585</u>
<u>Gravel &amp; Sand</u>	<u>14'</u>	<u>599</u>
<u>Hd Clay + Blue (Blue Clay)</u>	<u>101'</u>	<u>700</u>
<u>Red Hd. (Lime Rock)</u>	<u>15'</u>	<u>715</u>
<u>Gray Sand. Hard</u>	<u>11'</u>	<u>726</u>
<u>      "      "      "</u>	<u>10'</u>	<u>736</u>
<u>      "      "      "</u>	<u>26'</u>	<u>762</u>
<u>Hd Blue Clay</u>	<u>3'</u>	<u>765</u>

Information upon completion of well:


- (1) Diameter 2" inches.
- (2) Total Depth 765 feet.
- (3) Water Level Flowing feet below top of ground.
- (4) Cased to 742', Size 2"
- (5) Screen: Size 2", Length 20'
- (6) Were any formations sealed against pollution?  
       yes,        no.

Flowing 1500 G.P.H.  
Pumping 2000 G.P.H.  
By Air Pumping

If YES depth of formation       

Why       

Drillers Remarks:       



over

(Use Back Side)

Well No.

