

Harrison  
M 199  
1-67

MISSISSIPPI  
BOARD OF WATER COMMISSIONERS  
416 North State Street  
Jackson, Mississippi 39201

**CODED**

WATER WELL DRILLERS LOG

Jan. 10 1967 date well completed  
M&B Drilling Co. firm name  
Harrison county well located

LANDOWNER: M&B Apts  
(The Gallery) Biloxi  
Cabana (16)  
(mailing address)

WELL LOCATION:  
sec. 35 T. 7 S. R. 10 W.  
2 miles W of Biloxi  
(distance) (direction) (nearest town)


WELL PURPOSE: Hot Use  
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 6 1/4
- (2) total depth (feet) 706
- (3) static water level (feet) 18 below top of ground.
- (4) casing Steel 660  
(material) (depth)  
6 1/4 (size) if telescope see back.
- (5) screen 40 660  
(length) (depth to top)  
3" .008 Brass 1/2" dia  
(size) (material)
- (6) pump 7 1/2 175-Pump  
(HP) (yield gpm)  
220 V 3Ø  
(type power)
- (7) electric log No  
(yes or no)  
No  
(organization running log)
- (8) how well bottom plugged 2-3"  
Back Wash Valves

| description of formations encountered | from | to  |
|---------------------------------------|------|-----|
| Top Sand White                        | 0    | 35  |
| Blue Clay & Sea Shells                | 35   | 45  |
| Hard Blue Clay                        | 45   | 72  |
| Sandy Clay                            | 72   | 80  |
| Soft Blue Clay                        | 80   | 100 |
| Sand                                  | 100  | 120 |
| Blue Clay                             | 120  | 180 |
| Sand                                  | 180  | 184 |
| Blue Clay                             | 184  | 200 |
| Sand & Clay Brecker                   | 200  | 225 |
| Blue Clay                             | 225  | 395 |
| Fine Sand                             | 395  | 415 |
| Blue Clay                             | 415  | 463 |
| Sand                                  | 463  | 470 |
| Soft Swelling Hard Clay               | 470  | 485 |
| Blue Clay                             | 485  | 630 |
| Coarse Sand                           | 630  | 700 |

**CODED**



DRILLERS REMARKS:

If well telescopes, please sketch and show depths.

GROUND LEVEL

126 FT  
6" Black  
Steel  
Pipe

6x4  
118 - Lead  
126

44 Black  
Steel  
Pipe

660  
40 FT 3"  
Bronze 4' Iron  
Screen

760  
2-3"  
Back Wash  
Valves

|  |  |  |   |
|--|--|--|---|
|  |  |  | X |
|  |  |  |   |
|  |  |  |   |
|  |  |  |   |

SECTION 35

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,  
show locations of each on sketch.