

Harrison
M 219
7-67

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

July 6 1966 M&B Drilling Co. Harrison
date well completed firm name county well located

LANDOWNER: Forrest Cove
Estates - Brodie Road
Biloxi, Miss.
(mailing address)

WELL LOCATION:
sec. 17 T. 7 S. R. 9 W.
1 miles W of Setberville
(distance) (direction) (nearest town)

WELL PURPOSE: Subdivision
(home, irrigation, municipal, industrial)


WELL COMPLETION DATA:

- (1) diameter (inches) 4 X 3
- (2) total depth (feet) 370
- (3) static water level (feet) 20 below top of ground above
- (4) casing Steel 3.50
(material) (depth)
4 X 3 If telescope see back.
(size)
- (5) screen 20 350
(length) (depth to top)
3" .008 Brass Hederbar
(size) (material)
- (6) pump 5 80
(HP) (yield gpm)
220 10
(type power)
- (7) electric log No
(yes or no)
No
(organization running log)
- (8) how well bottom plugged 2-3"
Backwash Valves

description of formations encountered

	from	to
Surface	0	10
Sand & Gravel	10	20
White Clay	20	40
Grey Clay	40	50
Old Subway & Block Huck	50	60
Grey Clay	60	70
Blue Clay	70	90
Sand	90	100
Blue Clay	100	200
Sand	200	208
Blue Clay	208	232
Sand	232	239
Blue Clay	239	245
Sand	245	255
Blue Clay	255	270
Coarse Sand	270	282
Blue Clay	282	335
Grey Sand	335	370
Blue Clay	370	+

CODED



DRILLERS REMARKS:

