

Harrison
M 655
5-11-74

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

COASTAL DRILLING & SERVICE CO.

ROUTE 1 BOX 648

Harrison
county well located

5/11
date well completed

LANDOWNER: P. C. ... MISS.

Description of formations encountered	39537	
	from	to
top Soil	1	3
Red Soil	3	12
White Sand & gravel	12	25
(Coarse White Sand)	25	70
Shells	70	110
hard Blue Clay	110	214
Soft Blue Clay	214	290
(Coarse water Sand)	290	337

RT 2
Apt. Miss
(mailing address)

WELL LOCATION:
sec. 19 T 2 N R 10 E 135
S W
None miles W of Hanksboro
(distance) (direction) (nearest town)

WELL PURPOSE: Home
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 2"
- (2) total depth (feet) 337
- (3) static water level (feet) 37 below above top of ground.
- (4) casing 2" PVC 327'
(material) (depth)
- _____ If telescope see back.
(size)
- (5) screen 10' , 327'
(length) (depth to top)
- 2" , PVC
(size) (material)
- (6) pump One 12
(HP) (yield gpm)
- Elc
(type power)
- (7) electric log no
(yes or no)

_____ (organization running log)

(8) how well bottom plugged
2" hard wood valve


DRILLERS REMARKS:

RECORDED
JUL 10 1975

MISS. Bd OF WATER COMM

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.