

HAR. M 2000

WATER WELL DRILLERS LOG

?

Date: Dec 1, 1960, Driller: C.T. Switzer Well Co. County Harrison  
(Name)

(1) Owner of Land: J. H. Felts  
(Name)  
26 Briarfield Ave.  
W. Beach, Biloxi, Miss  
(Address)

(2) Location: 1/4, 1/4, Sec. T R  
17 8 10  
miles of  
(distance) (direction) (Nearest Town)

(3) Topography:  (Hilly)  (Flat)  (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Sand	18	18
Clay	5	23
Sand	15	38
Clay	25	63
Sand	15	78
Clay	5	83
Sand streaks	22	105
Clay	20	125
Clay + sand streaks	41	166
Clay	20	186
Sand streaks & clay	20	206
Clay	20	226
Sand streaks & clay	20	246
Clay	61	307
Sand streaks	35	342
Sand	18	360
Clay	49	409
Sand streaks	3	412
Clay	18	430
Good sand	40	470

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 470 feet.

(3) Water Level - 3 feet below top of ground.

(4) Cased to 470, Size 2 in


(5) Screen: Size 2, Length 10 ft.

(6) Were any formations sealed against pollution?  
yes, no.

If YES depth of formation 10 ft

Why Health Dept. Requirement

Drillers Remarks:



(Use Back Side)

Well No.

