

HARRISON MISSISSIPPI BOARD OF WATER COMMISSIONERS

M 2974

5-18-64

WATER WELL DRILLERS LOG

Date: 5-18, 1964, Driller: C. T. SWITZER WELL CO. County: Wilcox

(Name)

(1) Owner of Land: Amor C. Lee
 (Name)

no home on Bald Bluff
 (Address)

(2) Location: 79 T. R Sec. 79
 _____ miles _____ of _____
 (distance) (direction) (Nearest Town)

(3) Topography: (Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
 (Domestic Irrigation Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
clay	00	40
sand, fine	10	60
clay	60	70
clay w/ few sand lbs	80	100
clay	100	160
sand, fine	160	180
clay	180	200
sand, fine	200	230
clay	230	360
clay w/ few sand lbs	360	380
clay	380	600
sand	600	604
sand, no grad	604	616
clay	616	624
sand	624	664
shale w/ sand lbs	664	784
shale	684	724
shale + sand w/ layers rock	724	744
sand w/ 2' rock	744	754
sand w/ 2' rock	754	764
rock	764	767
sand	767	784
rock	784	785
sand	785	798
rock	798	799
sand	799	804
sand w/ layers rock	804	824
sand	824	855

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 855' feet.

(3) Water Level 6 1/2' + feet below top of ground.

(4) Cased to 855', Size 2"


(5) Screen: Size 2", Length 10'

(6) Were any formations sealed against pollution?
 yes, no.

If YES depth of formation _____

Why Health Dept. requirement

Drillers Remarks: _____



Well No.

