

HAR.

MISSISSIPPI BOARD OF WATER COMMISSIONERS

M

Mi

4-1-65

WATER WELL DRILLERS LOG

Date: April 1, 1965, Driller: C. T. Sirtgen Well Co. County Harrison

(Name)

(1) Owner of Land: D'Heriello Jr. Sr.  
(Name)

(Address)

(2) Location: 1/4, 1/4, Sec.      T      R       
miles      of       
(distance) (direction) (Nearest Town)

(3) Topography:       
(Hilly) (Flat) (Level)

(4) Purpose of Well:       
(Domestic Irrigation  
Municipal, Industrial, Other)

| Description & Color of Materials<br>Sand, Clay, Red Clay, Shell, etc. | Thick-<br>ness<br>Feet | Depth<br>Feet |
|---|------------------------|---------------|
| Sand  | 0                      | 5             |
| Clay  | 6                      | 11            |
| Sand, Clay, Shovel  | 11                     | 24            |
| Sand  | 24                     | 34            |
| Clay  | 34                     | 70            |
| Sand streaks  | 70                     | 91            |
| Clay  | 91                     | 113           |
| Mixed Sand & Clay   | 113                    | 135           |
| Sand streaks  | 135                    | 158           |
| Clay  | 158                    | 363           |
| Sand  | 363                    | 368           |
| Clay  | 368                    | 395           |
| Sand fine   | 395                    | 416           |
| Sand fair   | 416                    | 434           |
| Clay  | 434                    | 438           |
| Sand & Clay   | 438                    | 459           |
| Clay  | 459                    | 504           |
| Sand  | 504                    | 509           |
| Clay  | 509                    | 526           |
| Sand shale  | 526                    | 547           |
| Clay  | 547                    | 568           |
| Shale   | 568                    | 590           |
| Sand streaks  | 590                    | 611           |
| Sand  | 611                    | 621           |
| Shale   | 621                    | 632           |
| Clay & Shale  | 632                    | 654           |
| Fuller's Earth  | 654                    | 675           |
| Clay  | 675                    | 698           |
| Clay & Shale  | 698                    | 719           |
| Mixed Sand & Clay   | 719                    | 740           |
| Sand fair   | 740                    | 759           |
| Sand Good   | 759                    | 780           |

Information upon completion of well:

(1) Diameter 6x4 inches.

(2) Total Depth 861 feet.

(3) Water Level 6+ feet below top of ground.  
Top 150' 6"

(4) Cased to 861', Size 6x4


(5) Screen: Size 8ga., Length 40'

(6) Were any formations sealed against pollution?  
X yes,      no.

If YES depth of formation     

Why Health Department Requirements

Drillers Remarks:     



(Use Back Side)

Well No.

Sand Fair 780-802

Sand Fine 802-861