

~~1~~  
10-31-63

WATER WELL DRILLERS LOG

**CODED**

Date: 10-31, 1963, Driller: Lutter Well Works County Harrison  
(Name)

(1) Owner of Land: City of Long Beach  
(Name)

(Address) 12812

(2) Location: 1/4, 1/4, Sec. T R R

1 miles in Long Beach  
(distance) (direction) (Nearest Town)

(3) Topography: level  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Municipal  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Surface Clay	5	5
sand - clay streaks	63	68
Clay	136	204
sand	25	229
Clay	271	500
sand	25	525
Clay	16	541
sand	72	573
Clay	24	597
sand - clay streaks	52	649
Clay	98	747
sand - clay streaks	75	822
sand	105	927

Information upon completion of well:

(1) Diameter 8 x 12 inches.

(2) Total Depth 927 feet.

(3) Water Level \_\_\_\_\_ feet below top of ground.

(4) Cased to all, Size 8" <sup>top 156' of 12"</sup>

(5) Screen: Size 8", Length 60'

(6) Were any formations sealed against pollution?


yes,  no.

If YES depth of formation 156'

Why City requirements

Drillers Remarks:

**CODED**



Well No.

1111