

O 2001
7-19-62

WATER WELL DRILLERS LOG



Date: 7-19, 1962, Driller: C.T. SWITZER Well County Harrison
(Name)

(1) Owner of Land: Walter E. Ealey
(Name)
Long Beach, Miss.
(Address)

(2) Location: 812 $\frac{1}{4}$, 12 $\frac{1}{4}$, Sec. T R,
_____ miles _____ of _____
(distance) (direction) (Nearest Town)

(3) Topography: ✓
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
clay	00	10
Sand	10	36
clay	36	100
clay, red hard	100	140
clay	140	160
Sand, fine	160	190
Clay	190	200
Sand, fine	200	250
Clay	250	280
Sand, fine	280	310
Clay	310	420
Sand, fine	420	440
Sand, good	440	467

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 467' feet.

(3) Water level 1' 6" feet below top of ground.


(4) Cased to 464', Size 2"

(5) Screen: Size 2", Length 10'

(6) Were any formations sealed against pollution?
✓ yes, _____ no.

If YES depth of formation _____
Why Health Dept. Requirement

Drillers Remarks: _____



(Use Back Side)

Well No.

