

HINDS

Adams Egg Co.
became Cal-
Maine Foods

D
1-23-64

WATER WELL DRILLERS LOG

Date: 1-23-, 19 64, Driller: Layne-Central Co. County Hinds
(Name)

- (1) Owner of Land: Adams Egg Company
(Name)
Edwards, Mississippi
(Address)
- (2) Location: 1/4, 1/4, Sec. T R
miles, of
(distance) (direction) (Nearest Town)
- (3) Topography: (Hilly) (Flat) (Level)
- (4) Purpose of Well: Egg Farm
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
sandy clay	24	24
sand & gravel	8	32
clay	15	47
rock	4	51
clay	13	64
rock	2	66
clay	4	70
rock	3	73
clay	12	85
rock	3	88
clay-stks rock	33	121
hard brittle clay	77	198
fine sand-clay stk.	80	278
hard sandy clay	202	480
blue clay	272	752
hard sandy shale	84	836
shale stks fine sand	56	892
hard shale-stks sand	65	947
fine sand-shale	38	985
fine sand	104	1089

Information upon completion of well:

- (1) Diameter 8" inches.
- (2) Total Depth 1090' feet.
- (3) Water Level 95 feet below top of ground.
- (4) Cased to 1035', Size 8"
- (5) Screen: Size 6", Length 41'
- (6) Were any formations sealed against pollution?
X yes, no.

If YES depth of formation 1035'

Why required

Drillers Remarks:



(Use Back Side)

Well No.

D.
 2-13-64

K21
 WATER WELL DRILLERS LOG

Date: 2-13-1964, Driller: Layne-Central Co. County: Hinds
 (Name)

(1) Owner of Land: Adams Egg Company
 (Name)
 Edwards, Mississippi
 (Address)
 (2) Location: 1/4, 1/4, Sec. T R
 miles of
 (distance) (direction) (Nearest Town)
 (3) Topography:
 (Hilly) (Flat) (Level)
 (4) Purpose of Well: Egg Processing Plant
 (Domestic Irrigation
 Municipal, Industrial, Other)


Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
sandy clay	24	24
sand-gravel	8	32
clay	15	47
rock	4	51
clay	13	64
rock	2	66
clay	4	70
rock	3	73
clay	12	85
rock	3	88
clay-stks rock	33	121
hard brittle clay	77	198
fine sand-clay stks	80	278
hard sandy clay	202	480
blue clay	272	752
hard sandy shale	84	836
shale-stks fine sand	56	892
hard shale-stks sand	65	947
fine sand-shale	38	986
fine sand	104	1089

Information upon completion of well:

(1) Diameter 8" inches.
 (2) Total Depth 1090 feet.
 (3) Water Level 95 feet below top of
 ground.
 (4) Cased to 1035', Size 8"
 (5) Screen: Size 6", Length 41'
 (6) Were any formations sealed against pollution?
 X yes, no.

If YES depth of formation 1035'
 Why required
 Drillers Remarks:

CODED



(Use Back Side)

Well No.