

HINDS

MISSISSIPPI BOARD OF WATER COMMISSIONERS

F 2

6-64

WATER WELL DRILLERS LOG


CODED 6

R.G.

Date: JUNE, 1964, Driller: MCNEECE DRILLING Co. County: HINDS

(Name Co.)

(1) Owner of Land: <u>WYATT, Williamson</u> (Name)	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
RT. 1, CLINTON MISS (Address)	SURFACE SOIL	6	6
(2) Location: <u>SE 1/4, NW 1/4, Sec. 1 T. 6N R. 2W</u>	RED CLAY	6	12
<u>3</u> miles <u>N</u> of <u>CLINTON</u> (distance) (direction) (Nearest Town)	WHITE SAND + GRAVEL	28	40
(3) Topography: <u>Hilly</u> (Hilly) (Flat) (Level)	GREY SHALE	26	66
(4) Purpose of Well: <u>DOMESTIC</u> (Domestic Irrigation Municipal, Industrial, Other)	SHALE + SAND	21	87
Information upon completion of well:	SAND	57	144
(1) Diameter <u>4 1/2</u> inches.	GREY SHALE	454	598
(2) Total Depth <u>872</u> feet.	SHALE SHELL + SAND	17	617
(3) Water Level <u>158</u> feet below top of ground.	SHALE	8	625
(4) Cased to <u>342'</u> , Size <u>4"</u> <u>342' to 872' - 2"</u>	SHALE + SAND	13	638
(5) Screen: Size <u>2"</u> , Length <u>20'</u>	SHALE	21	659
(6) Were any formations sealed against pollution? <u>no</u>	FINE SAND	10	669
If YES depth of formation _____	SHALE	11	680
Why _____	SHALE + SAND	16	696
Drillers Remarks: _____	FINE SAND	25	721
_____	" "	74	795
_____	SAND	77	872



Well No. 74

(Use Back Side)

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.