


MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

Date: 6-11-61, 1961, Driller: James M^s Nees County Hinds

(Name)

McLendon Broadcasting Co.		Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: _____ (Name)		Surface soil	16	
<u>JACKSON</u> (Address)		Blue shale	17	33
(2) Location: <u>SW 1/4, SW 1/4, Sec. 21 T⁶ R²W</u>		Rock	1	34
<u>6</u> miles <u>West</u> of <u>Clinton</u> (distance) (direction) (Nearest Town)		Grey shale	17	45
(3) Topography: _____ (Hilly) (Flat) (Level)		Rock-shale streaks	21	66
(4) Purpose of Well: <u>Domestic Home</u> (Domestic Irrigation Municipal, Industrial, Other)		Grey shale	10	76
Information upon completion of well:		Grey sandy shale	4	80
(1) Diameter: <u>2</u> inches	WELL DEPTH 271	Grey shale	56	136
(2) Total Depth: <u>271</u> feet		Grey sandy shale	3	139
(3) Water Level: <u>Flowed</u> feet below top of ground.		Grey shale	4	143
(4) Cased to: <u>157</u> , Size <u>2"</u>		Grey shale with SD SHRS	14	157
(5) Screen: Size <u>006 2"</u> , Length <u>5'</u>		Sand	5	162
(6) Were any formations sealed against pollution? _____yes, _____no.		Sand with shale streaks	4	166
If YES depth of formation _____		Grey shale	105	271
Why _____				
Drillers Remarks: _____		7fts. 2" Galv pipe	147	
		1 - - - - -	10	
			157	
		1-2", 006		
		Johnston stainless		
		steel screen	5	
			162	
		1-2" Back wash		
		Valve-2" coupling		
		and 2" Nipple	1	
			163	



(Use Back Side)

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.