


G 69
9-15-64

WATER WELL DRILLERS LOG

CODED

Date: SEPT 15, 1964, Driller: Edna C. Hall County HINDS
HALL DRILLING CO.

(1) Owner of Land: <u>SEAB REYNOLDS</u> <small>(Name)</small>	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>204 LEA CIRCLE</u> <small>(Address)</small>	<u>SURFACE SOIL</u>	<u>6</u>	<u>6</u>
(2) Location: <u>N 1/2 1/4 Sec. 8 T6DR14W</u> <u>2</u> miles <u>N.E.</u> , of <u>CLINTON</u> . <small>(distance) (direction) (Nearest Town)</small>	<u>GRAY MARL</u>	<u>29</u>	<u>35</u>
(3) Topography: <u>FLAT</u> <small>(Hilly) (Flat) (Level)</small>	<u>YAZOO CLAY</u>	<u>355</u>	<u>390</u>
(4) Purpose of Well: <u>DOMESTIC</u> <small>(Domestic Irrigation Municipal, Industrial, Other)</small>	<u>MOODY'S BRANCH</u>	<u>10</u>	<u>400</u>
	<u>SHALE & LIGNITE</u>	<u>22</u>	<u>422</u>
	<u>FINE GRAIN SAND</u>	<u>10</u>	<u>432</u>
	<u>SAND ROCK & SHALE</u>	<u>57</u>	<u>489</u>
	<u>SAND FINE GRAIN</u>	<u>20</u>	<u>509</u>
	<u>SAND & SHALE</u>	<u>21</u>	<u>530</u>
	<u>SHALE</u>	<u>35</u>	<u>565</u>
	<u>FINE SAND</u>	<u>22</u>	<u>587</u>
	<u>MED GRAIN SAND</u>	<u>49</u>	<u>636</u>
	<u>COURSE SAND</u>	<u>40</u>	<u>676</u>
Information upon completion of well:			
(1) Diameter <u>4 X 2</u> inches.			
(2) Total Depth <u>676</u> feet.			
(3) Water Level <u>181</u> feet below top of ground.			
(4) Cased to <u>355</u> , Size <u>4"</u> <u>301</u> <u>2"</u>			
(5) Screen: Size - <u>2"</u> , Length <u>20'</u>			
(6) Were any formations sealed against pollution?			
_____ yes, <u>X</u> no.			
If YES depth of formation _____			
Why _____			
Drillers Remarks: _____			



(Use Back Side)

Well No. _____