

HINDS

MISSISSIPPI BOARD OF WATER COMMISSIONERS

H

WATER WELL DRILLERS LOG

H 300

7-25-60

Date: 7/25, 1960, Driller: Jonnie Beasley County Hinds  
(Name)

*Forest Drilling*

(1) Owner of Land: Mrs. Hazel Gibson  
(Name)

Rt. 2, Box 380 Country Club  
Road. Jackson, Miss.  
(Address)

(2) Location: 1/4, 1/4, Sec. T R

2.2 miles North of Jackson  
(distance) (direction) (Nearest Town)

(3) Topography: X  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Home.  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Brown Silt & Clay.	0	
Blue Clay.	30	130
Shell, Lime & Shale.	110	130
Shale & Lignite.	130	153
Fine Sand & Stks. Shale.	153	170
Shale & Stks. Silt.	170	175
Black Clay.	175	200
Lime, Rock & Black Clay.	200	250
Shale & Stks. Silt.	250	307
Silt Sand & Stks. Shale.	307	327
Blue Shale.	327	471
Blue Shale.	471	487
Rock.	485	487
Shale & Stks. Rock.	487	512
Shale & Stks. Sand.	512	535
Fine Sand.	535	575
Good Sand. (Screen Set)	575	590

Information upon completion of well:

(1) Diameter 2" inches.

(2) Total Depth 590 feet.

(3) Water Level 160 feet below top of ground.

(4) Cased to 575', Size 2"


(5) Screen: Size 2", Length 15'

(6) Were any formations sealed against pollution?  
yes, X no.

If YES depth of formation

Why

Drillers Remarks: Fine well.



(Use Back)

this copy to Board of Water Commissioners 429 Miss.