

HINDS

H-135

7-18-62

Loc# 443


WATER WELL DRILLERS LOG

Forest Drilling

Date: 7/16 to 7/18/1962, Driller: Johnnie Beasley County Hinds.

(Name)

	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>U. S. Government</u> <u>V. A. Hospital</u> (Name) <u>Jackson, Miss.</u> (Address)	Yellow clay.	25-	25
(2) Location: <u>1/4, 1/4, Sec 26 T6 R1</u> <u>pital on Hwy. 51 north of Jackson.</u> _____ miles _____ of _____ (distance) (direction) (Nearest Town)	Blue clay.	35-	60
(3) Topography: <u>x</u> (Hilly) (Flat) (Level)	Lime & clay.	10-	70
(4) Purpose of Well: <u>Municipal.</u> (Domestic Irrigation Municipal, Industrial, Other)	Lime & shell.	15-	85
Information upon completion of well:	Brown clay.	109-	194
(1) Diameter <u>4</u> inches.	Brown clay & stks. lime.	31-	225
(2) Total Depth <u>768</u> feet.	Black clay.	61-	286
(3) Water Level <u>220</u> feet below top of ground.	Shale & mucky sand.	21-	307
(4) Cased to <u>728'</u> , Size <u>4"</u>	Silt sand.	12-	319
(5) Screen: Size <u>3"</u> , Length <u>40'</u>	Shale.	8-	327
(6) Were any formations sealed against pollution? <u>700' of that this well was grouted according to specifications.</u>	Blue clay.	62-	389
If YES depth of formation _____	Blue shale & stks. lime.	41-	430
Why _____	Shale & stks. rock.	20-	450
Drillers Remarks: <u>Good</u>	Fine sand.	20-	470
FOREST DRILLING SERVICE	Silt & shale.	84-	554
P. O. Box 5717	Shale.	8-	562
PEARL BRANCH	Fine sand.	10-	572
JACKSON 8, MISS.	Shale.	3-	575
MISS. BOARD OF WATER COMM.	Shale & stks. silt.	22-	597
RECEIVED	Fine sand.	70-	667
AUG 29 1962	Fine sand & stks. shale.	20-	687
WELL No. _____	Fine sand.	33-	729
(Use Back Side)	Sand. (Screen setting.)	48-	768
Retain this copy for your office files.			



FOREST DRILLING SERVICE
P. O. Box 5717
PEARL BRANCH
JACKSON 8, MISS.

Well No.