

HINDS MISSISSIPPI BOARD OF WATER COMMISSIONERS

H-138

6-63

WATER WELL DRILLERS LOG


(R.G.)

Date: JUNE, 1963, Driller: MCNEECE DRILLING County HINDS
(Name Co.)

	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>HINDS COUNTY WATER</u> <small>(Name) Co.</small>	SURFACE SOIL	6	6
P.O. Box 8127, JACKSON MISS <small>(Address)</small>	YELLOW MARL	32	38
(2) Location: <u>NW 1/4</u> , <u>1/4</u> , Sec. <u>4</u> <u>TORIE</u> <u>3</u> miles <u>WEST</u> of <u>TOWGAHOO</u> <small>(distance) (direction) (Nearest Town)</small>	GREY SHALE	327	365
	SAND SHELL + SHALE	25	390
	LIGNITE + SAND	21	411
	SHALE SAND + LIGNITE	105	516
(3) Topography: <u>HILLY</u> <small>(Hilly) (Flat) (Level)</small>	FINE SAND	43	559
	SAND + LIGNITE		581
(4) Purpose of Well: <u>MUNICIPAL</u> <small>(Domestic Irrigation Municipal, Industrial, Other)</small>	SAND + LIGNITE	65	624
	COARSE SAND	66	690

Information upon completion of well:

- (1) Diameter 6x4" inches.
- (2) Total Depth 690 feet.
- (3) Water Level 219 feet below top of ground.
- (4) Cased to 400', Size 6"
400' - 690' - 4"
- (5) Screen: Size 4", Length 40'
- (6) Were any formations sealed against pollution?
 yes, no.



If YES depth of formation _____
 Why _____
 Drillers Remarks: _____

Well No. 53

(Use Back Side)