

HINDS

MISSISSIPPI BOARD OF WATER COMMISSIONERS

H 2002

WATER WELL DRILLERS LOG

8-27-62

Forest Drilling

Date: 8/24, 8/27, 1962, Driller: Johnnie Beasley County Hinds

(Name)

(1) Owner of Land: WJDX Radio Station
(Name)
Jackson, Mississippi
(Address)
This well located on Beasley road
(2) Location: 1/4, 1/4, Sec. T&R 1/2
in North Jackson at Radio towers.
_____ miles _____ of _____
(distance) (direction) (Nearest Town)
(3) Topography: X
(Hilly) (Flat) (Level)
(4) Purpose of Well: Domestic. Home
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Brown silt & clay.	35	35
Blue clay.	129	164
Shale & stks. lime.	20	184
Shale, shell & lignite.	60	244
Shale, soft clay & lignite	104	348
Shale & stks. sand.	22	370
Fine sand.	21	391
Fine sand & stks. shale.	31	422
Fine sand.	10	432
Fine sand & stks. shale.	51	483
Shale.	155	638
Silt & shale.	10	648
Sand. (Screen setting.)	49	697

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 697 feet.

(3) Water level _____ feet below top of ground.

(4) Cased to 677', Size 2"

(5) Screen: Size 2", Length 20'

(6) Were any formations sealed against pollution?
_____ yes, X no.


If YES depth of formation _____

Why _____

Drillers Remarks: Good well.

FOREST DRILLING SERVICE

P. O. Box 5717
PEARL BRANCH
JACKSON 8, MISS.



Well
158

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson.