

HINDS  
M 76

MISSISSIPPI BOARD OF WATER COMMISSIONERS

12-10-62

WATER WELL DRILLERS LOG **CODED CODED**

Date: 12-10- 1962, Driller: James McNeese County Hinds

E log #157

(Name)

(1) Owner of Land E.B. Mitchell  
(Name)  
5137 LURLINE DRIVE  
(Address) JACKSON

(2) Location: SE 1/4, NE 1/4, Sec. 29 5<sup>N</sup> R1W  
5 miles West of JACKSON  
(distance) (direction) (Nearest Town)

(3) Topography: \_\_\_\_\_  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Surface soil	20	20
Clay	20	40
Grey shale & Lime sh.	60	100
Grey sdy shale	20	120
SAND	10	130
Grey sdy sh	10	140
Grey shale	60	200
SAND	25	225
SAND <b>CODED CODED</b>	30	255
Grey shale	425	680
Grey sdy shale	20	700
Grey sh	7	707
Grey sdy shale	40	747
SAND	45	792
Grey shale	7	799
15 JOINTS 4"	315'	
1 4"x2" swedge	1'	
21 JOINTS 2"	441'	
1 - - -	11'	
1008. S.S screen	768'	
	20'	
	788'	
1 2" Nipple + B.R.V	6'	
	794'	

Information upon completion of well:

(1) Diameter 4"x2" inches.

(2) Total Depth 799 feet.

(3) Water Level 109 feet below top of ground.

(4) Cased to 768, Size 4"x2"


(5) Screen: Size 2.008, Length 20

(6) Were any formations sealed against pollution?  
\_\_\_\_\_ yes, \_\_\_\_\_ no.

If YES depth of formation

Why

Drillers Remarks:



(Use Back Side)

Well No.