

Hinds  
P 56  
3-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

COPIED  
COPIED

Date: 2/25, 1966, Driller: Faust Drilling County Hinds  
(Name)

		Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land:	<u>Dalley Farming School</u> (Name)			
	<u>Dalley, Miss</u> (Address)	<u>Chalky Clay</u>		<u>25</u>
(2) Location:	<u>1/4, 1/4, Sec. 4 T. R.</u> <u>at Dalley Farming School</u>	<u>blue clay, fine, shell</u>		<u>105</u>
	<u>miles</u> (distance) <u>of</u> (direction) <u>(Nearest Town)</u>	<u>Rock + some</u>		<u>158</u>
(3) Topography:	(Hilly) (Flat) (Level)	<u>Shale + 5th. lime</u>		<u>194</u>
(4) Purpose of Well:	<u>School</u> (Domestic Irrigation Municipal, Industrial, Other)	<u>fine sand</u>		<u>205</u>
		<u>Shale + Lignite</u>		<u>210</u>
		<u>Shale + soft clay</u>		<u>220</u>
		<u>Shale</u>		<u>245</u>
		<u>Shale + 5th. silt</u>		<u>256</u>
		<u>Shale</u>		<u>266</u>
		<u>Silt</u>		<u>276</u>
		<u>Shale - 7' zone</u>		<u>279</u>
		<u>Blue Clay</u>		<u>307</u>
		<u>7' zone Clay</u>		<u>410</u>
		<u>Shale</u>		<u>719</u>
		<u>Shale + 5th. rock</u>		<u>760</u>
		<u>Soft Shale + shell</u>		<u>780</u>
		<u>Shale</u>		<u>820</u>
		<u>Shale + soft clay</u>		<u>841</u>
		<u>Shale</u>		<u>862</u>
		<u>Rock</u>		<u>882</u>
		<u>Shale</u>		<u>884</u>
		<u>Soft Clay + Shale</u>		<u>953</u>
		<u>Soft Clay + Sand</u>		<u>987</u>
		<u>5th. clay + sand</u>		<u>1008</u>
		<u>7' zone + 5th. shale</u>		<u>1050</u>
		<u>Fine silt</u>		<u>1080</u>


Information upon completion of well:

- (1) Diameter 4 inches.
- (2) Total Depth 1080 feet.
- (3) Water Level 70 feet below top of ground.
- (4) Cased to 1040, Size 4"
- (5) Screen: Size 4", Length 40ft.
- (6) Were any formations sealed against pollution?  
no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.