

HINDS MISSISSIPPI BOARD OF WATER COMMISSIONERS

P. 2004


2-1-63

WATER WELL DRILLERS LOG

Date: 2-1-63, 19___, Driller: James McNeas County: Hinds

(Name)

(1) Owner of Land	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Charles Stamps</u> (Name)	<u>Surface soil-clay</u>	<u>20</u>	<u>20</u>
<u>Learned Miss</u> (Address)	<u>Clay</u>	<u>15</u>	<u>35</u>
(2) Location: <u>NW 1/4, SW 1/4, Sec. 13 A N W</u> <u>2</u> miles <u>East</u> of <u>Learned</u> (distance) (direction) (Nearest Town)	<u>Sand</u>	<u>5</u>	<u>40</u>
	<u>Blue shale</u>	<u>32</u>	<u>72</u>
	<u>Sand</u>	<u>18</u>	<u>90</u>
	<u>Blue shale</u>	<u>28</u>	<u>118</u>
(3) Topography: <input checked="" type="checkbox"/> (Level) (Hilly) (Flat)	<u>Grey sdy sh</u>	<u>9</u>	<u>127</u>
	<u>Sand</u>	<u>2</u>	<u>129</u>
(4) Purpose of Well: <u>Domestic Home</u> (Domestic Irrigation Municipal, Industrial, Other)	<u>Brown shale</u>	<u>53</u>	<u>182</u>
	<u>Rock. Sand shells</u>	<u>13</u>	<u>195</u>
	<u>Grey shale</u>	<u>9</u>	<u>204</u>
	<u>Rock</u>	<u>10</u>	<u>214</u>
	<u>Grey shale</u>	<u>2</u>	<u>216</u>
	<u>Rock sh str</u>	<u>42</u>	<u>258</u>
	<u>Grey shale</u>	<u>5</u>	<u>263</u>
	<u>Grey sdy sh</u>	<u>38</u>	<u>301</u>
	<u>Grey shale</u>	<u>18</u>	<u>319</u>
	<u>Sand</u>	<u>3</u>	<u>322</u>
	<u>Shale</u>	<u>29</u>	<u>351</u>
	<u>Sand</u>	<u>7</u>	<u>358</u>
	<u>Grey shale</u>	<u>34</u>	<u>392</u>
Information upon completion of well:			
(1) Diameter <u>2</u> inches.			
(2) Total Depth <u>392</u> ^{Hole} feet.			
(3) Water Level <u>80</u> feet below top of ground.			
(4) Cased to <u>348</u> ^{Well} Size <u>2"</u>			
(5) Screen: Size <u>2" 007</u> ³³⁸ , Length <u>10</u>			
(6) Were any formations sealed against pollution?			
_____ yes, _____ no. <input checked="" type="checkbox"/>	<u>16 ft 2"</u>	<u>326</u>	
	<u>1 - -</u>	<u>12</u>	<u>6"</u>
If YES depth of formation	<u>1 - 21" 007.55 screen</u>	<u>10</u>	<u>348' 6"</u>
Why			<u>358' 6"</u>
Drillers Remarks:			



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.