

HINDS MISSISSIPPI BOARD OF WATER COMMISSIONERS


R
10-26-60

WATER WELL DRILLERS LOG

R 300

Date: 10/26, 1960, Driller: Johannie Beasley County Rankin
(Name Hinds)

	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>Brookwood Co. Club</u> (Name) <u>Jackson, Miss.</u> (Address)	Silt.	0	10
	Chalk & stks. gravel.	10	35
	Lime & lime rock.	35	70
(2) Location: <u>1/4</u> , <u>1/4</u> , Sec. <u> </u> T. <u> </u> R. <u> </u>	Sand.	70	75
<u>10</u> miles <u>S. W.</u> , of <u>Jackson</u> (distance) (direction) (Nearest Town)	Blue clay.	75	100
	Blue clay & lignite.	100	160
	Blue clay.	160	287
(3) Topography: <u>X</u> (Hilly) (Flat) (Level)	Blue shale.	287	592
(4) Purpose of Well: <u>Domestic.</u> (Domestic Irrigation Municipal, Industrial, Other)	Shell, lime & Sand,	592	622
	Shale & stks. sand.	622	637
	Shale.	637	663
Information upon completion of well:	Shale & stks. silt.	663	705
(1) Diameter <u>2</u> inches.	Shale & stks. sand.	705	760
(2) Total Depth <u>785</u> feet.	Sand & stks. shale.	760	770
(3) Water Level <u>220</u> feet below top of ground.	Sand. (Sfeen set).	770	789
(4) Cased to <u>770'</u> , Size <u>2"</u>	Shale.	789	793
(5) Screen: Size <u>2"</u> , Length <u>15'</u>	Sand.	793	800
(6) Were any formations sealed against pollution? <u> </u> yes, <u>X</u> no.			
If YES depth of formation <u> </u>			
Why <u> </u>			
Drillers Remarks: <u>Good well.</u>			



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.