

HINDS

R 2003

8-23-62

WATER WELL DRILLERS LOG

Forest Drilling

Date 8/20 to 8/23 1962, Driller: Johnnie Beasley County Hinds

(Name)

(1) Owner of Land: Edward T. Offner
 Go down Hwy. 51 ^(Name) to Elton exit
 turn off and take frontage rd. to
 next bridge across Hwy. 51. Go ^(Address) 4N-1
 straight ~~across~~ across Hwy. and
 follow straight rd. first house on
 left. 15 miles South, of Jackson
 (distance) (direction) (Nearest Town)

(3) Topography: X
 (Hilly) (Flat) (Level)


(4) Purpose of Well: Domestic, Home
 (Domestic Irrigation
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Brown silt.	18	18
Blue clay & stks. silt.	40	58
Silt sand.	7	65
Blue clay.	242	307
Blue shale.	213	520
Shale.	55	575
Fine sand.	10	585
Sand & shale.	10	595
Fine sand.	21	616
Shale.	1	617
Fine sand.	3	620
Sand. (Screen setting.)	20	640

Information upon completion of well:

- (1) Diameter 2 inches.
- (2) Total Depth 640 feet.
- (3) Water Level 135 feet below top of ground.
- (4) Cased to 630', Size 2"
- (5) Screen: Size 2", Length 10'
- (6) Were any formations sealed against pollution?
no.

If YES depth of formation _____
 Why _____
 Drillers Remarks: Good well.



FOREST DRILLING SERVICE
 P. O. Box 5717
 PEARL BRANCH
 JACKSON 8, MISS.

Retain this copy for your office files.

(Use Back Side)

Well No.