


HINDS MISSISSIPPI BOARD OF WATER COMMISSIONERS

U 2005
10-30-63

WATER WELL DRILLERS LOG



Date: Oct. 30, 1963, Driller Burney Water Well Serv. Co. Hinds County

(1) Owner of Land: E. Ransom
(Name)
Terry, Miss.
(Address)
Pine Grove Road
(2) Location: 1/4, 1/4, Sec. 13N24W
4 miles west, of Terry
(distance) (direction) (Nearest Town)
(3) Topography: Hilly
(Hilly) (Flat) (Level)
(4) Purpose of Well: Domestic Home
(Domestic Irrigation, Municipal, Industrial, Other)

Description & Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Red top soil	8	8
Iron rock	3	11
Grey clay	11	22
Yellow clay	8	30
Layers of sand	6	36
Grey clay	7	43
Clay & sand layer	23	66
Hard rock	3	69
Sand & clay layers	10	79
Hard rock	5	84
All good sand	26	110
Blue shale	2	112

Information upon completion of well:

(1) Diameter 4 inches.
(2) Total Depth 112 feet.
(3) Water Level 58 feet below top of ground.
(4) Cased to 94', Size 2"
(5) Screen: Size 2 1/2", Length 17'

(6) Were any formations sealed against pollution?
x yes, _____ no.

If YES depth of formation From surface
Why to prevent surface pollution

Drillers Remarks:

(Use Back Side)

Well No.