

JACKSON

A 9

10-6-60

WATER WELL DRILLERS' LOG

Date: Oct. 6, 1960, Driller: C.T. Sartin Well Co. County Jackson
39 (Name)

(1) Owner of Land: Calvin Blair
(Name)
 2 1/2 miles west of Highway 57-13 miles
 north of Vancleave on 4 mile branch
(Address)

(2) Location: NE 1/4, SW 1/4, Sec. 14 T4SR8W
 12 miles N of Vancleave
(distance) (direction) (Nearest Town)

(2) Topography: (Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
(Domestic Irrigation
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
red surface clay	0	13
yellow sand	13	25
light gray clay	25	38
blue clay	38	240
fine clay	240	248
sandy shell	248	387
stratified	387	390
good sand	390	398
sand with shell	398	436
hard - good	436	466

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 466' feet.

(3) Water Level -90' feet below top of ground.

(4) Cased to 466', Size 2"


(5) Screen: Size 10 ga, Length 10'

(6) Were any formations sealed against pollution?
 yes, no.

If YES depth of formation 10 feet

Why Res. to dept. requirement

Drillers Remarks:



Well No.

