

JACKSON  
E 25

WATER WELL DRILLERS LOG

Date: Apr. 6, 1962, Driller: M & B Drilling Co. County Jackson  
(Name)

4-6-62

(1) Owner of Land: August Parker  
(Name)  
700 W. Bayview, Biloxi, Miss.  
(Address)

(2) Location: 1/4, 1/4, Sec. 25 45 17 10  
18 miles NE of Biloxi  
(distance) (direction) (Nearest Town)

(3) Topography: Hilly  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Yellow Clay</u>	<u>37</u>	<u>37</u>
<u>White Clay</u>	<u>3</u>	<u>40</u>
<u>Blue Clay</u>	<u>70</u>	<u>110</u>
<u>Clay &amp; Sand Breaks</u>	<u>10</u>	<u>120</u>
<u>Blue Clay</u>	<u>20</u>	<u>140</u>
<u>Grey Sand</u>	<u>10</u>	<u>150</u>
<u>Blue Clay</u>	<u>5</u>	<u>155</u>
<u>Grey Sand</u>	<u>44</u>	<u>199</u>
<u>Blue Clay 199 on</u>		

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 199 feet.

(3) Water Level 43 feet below top of ground.

(4) Cased to 189, Size 2"


(5) Screen: Size 2" 85/6T, Length 10 FT.

(6) Were any formations sealed against pollution?  
\_\_\_\_\_ yes, \_\_\_\_\_ no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.

