

Jackson
K 2050
12/16/77

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

WATER WELL DRILLERS LOG

12/16/77 date well completed
Coastal Drilling Firm Name
Jackson county well located

LANDOWNER: Donald Negrin
Pt 4 Bal 2437
Ocean Spring Min
(mailing address)

WELL LOCATION:
sec. 1 T. 6x R. 7
3 miles (distance) W (direction) (nearest town)
Micro Wave Star

WELL PURPOSE: home
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 4 1/2"
 - (2) total depth (feet) 1000'
 - (3) static water level (feet) 35' below top of ground
 - (4) casing PVC, 985'
(material) (depth)
4 1/2" If telescope see back.
(size)
 - (5) screen 15', 985'
(length) (depth to top)
2" PVC
(size) (material)
 - (6) pump 1 1/2 28
(HP) (yield gpm)
Ele
(type power)
 - (7) electric log no
(yes or no)
- (organization running log)

(8) how well bottom plugged
2" back with valve

DRILLERS REMARKS:
every good well

description of formations encountered	from to	
	feet	feet
top soil	1	3
Red Clay	3	20
Coarse white Sand	20	90
Super Sand	90	130
Soft Blue Clay	130	330
fine water sand	330	365
hard blue clay	365	510
fine water sand	510	550
hard blue clay	550	770
fine water sand	770	800
Rock + Schale	800	810
hard blue clay	810	910
fine sand shell	910	950
fine water sand	950	1000

RECEIVED

JAN 16 1978

MISS. BD. OF WATER COMM

If well telescopes please sketch and show depths.

GROUND LEVEL


200 ft 4" PVC
Casing

785' 2" PVC
Casing

15' 2" PVC
Screen

2" back Wash
Valve

If more than one screen, show locations of each on sketch.



SECTION _____

Please indicate well location X

ADDITIONAL INFORMATION

Multiple horizontal lines for recording additional information.