


JACKSON
K 2096
6-4-80
6-4-

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201



WATER WELL DRILLERS LOG

date well completed: 6-4-80
firm name: 80 Coast Water Well Serv. Inc.
county well located: Jackson

LANDOWNER: Richard Sulman
Ph. 4 - Box 94 B -
Ocean Springs, Miss.
(mailing address) 39564
WELL LOCATION:
sec. 33 T. 6 R. 7 W.
6 miles North of Hattiesburg
(distance) (direction) (nearest town)

WELL PURPOSE: Home
(home, irrigation, municipal, industrial)

- WELL COMPLETION DATA:
- (1) diameter (inches) 2"
 - (2) total depth (feet) 395'
 - (3) static water level (feet) 56' below top of ground
 - (4) casing PVC 385' (material) (depth)
 - (5) screen 2" (size) 10' (length) 385' (depth to top) PVC (material)
 - (6) pump 1 hp. 8 (HP) (yield gpm) Elect. (type power)
 - (7) electric log No. (yes or no)

(8) how well bottom plugged: backwash valve
DRILLERS REMARKS:

Description of formations encountered	from	to
Top soil	0	3'
Red Clay	3	10'
blue clay	10	66'
Red Med. sand	66	79'
Blue Clay	79	109'
Red Med. sand	109	130'
Red Med sand	130	192'
Blue Clay	192	320'
Blue Clay & streak of sand	320	342'
Gray Med sand	342	363'
Gray coarse sand	363	395'

DEPT. OF NATURAL RESOURCES
BUREAU OF LAND & WATER RESOURCES

MAR 20 1981



