

JACKSON MISSISSIPPI BOARD OF WATER COMMISSIONERS

N 138

8-11-62

WATER WELL DRILLERS LOG

Date: Aug 11, 1962, Driller: M & B Drilling Co. County Jackson
(Name)

(1) Owner of Land: John Hambalch
(Name)
Big Ridge Rd. Biloxi, Miss
(Address)

(2) Location: NE 1/4, SW 1/4, Sec 10 T5R9E4
2 miles NE of Biloxi
(distance) (direction) (Nearest Town)

(3) Topography: Flat to Rolling
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
(Domestic Irrigation Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay	8	8
White Sand	12	20
White Clay	10	30
White Sand	30	60
Sandstone	1	61
Blue Clay	339	700
Blue clay & clamshells about 1/2 to 1, but sometimes:	80	480
Clamshells		
Blue Clay	95	575
Coarse Grey Sand	25	600

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 590 feet.

(3) Water Level 18 feet below top of ground.

(4) Cased to 580, Size 2"


(5) Screen: Size 2" X 3/16", Length 10 FT.

(6) Were any formations sealed against pollution?
 _____ yes, _____ no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____



(Use Back Side)

Well No.

Handwritten text at the top of the page, possibly a title or header.

Main body of handwritten text, appearing as a list or series of entries.

Handwritten text in the lower right quadrant, possibly a signature or date.