

45

Jackson
N 194
11-67

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

JD

WATER WELL DRILLERS LOG

11-27-67 date well completed
COAST WATERWELL SERVICE firm name
JACKSON county well located

LANDOWNER: Ronald HALE

Rural Route 3 Bay/MS

Biloxi Miss.
(mailing address)

WELL LOCATION:

sec. 14 T 7 N R 9 E
S W
5 miles West of Ocean Springs
(distance) (direction) (nearest town)

WELL PURPOSE: Home
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 2"
- (2) total depth (feet) 220'
- (3) static water level (feet) 10 below top of ground. above
- (4) casing GALV. 210'
(material) (depth)
2"
(size) If telescope see back.
- (5) screen 10' 210'
(length) (depth to top)
2" STAINLESS STEEL
(size) (material)
- (6) pump 1/2 10
(HP) (yield gpm)
Elect.
(type power)
- (7) electric log NO
(yes or no)


(organization running log)

(8) how well bottom logged 2" BACK
WASH VALE

description of formations encountered

from to

RED CLAY	0	15
MED. SAND	15	32
BLUE CLAY	32	34
MED. SAND	34	40
BLUE CLAY	40	78
FINE SAND	78	89
BLUE CLAY	89	202
MED. SAND	202	220



DRILLERS REMARKS:

If well telescopes please sketch and show depths.

GROUND LEVEL

NW SW

X			

SECTION 14

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.