

CODED

MISSISSIPPI

BOARD OF WATER COMMISSIONERS

416 North State Street

Jackson, Mississippi 39201

FEB 17 1972

WATER WELL DRILLERS LOG

MISS. BD. OF

JACKSON
N 363
1-22-72

1-22 1972
date well completed

Switzer Well Co.
firm name

JACKSON
county well located

LANDOWNER: J. W. Welles
Rose farm Rd.
Ocean Springs, Miss.
 (mailing address)

description of formations encountered

from to

sand-clay mixed	0	23
clay	23	66
sand	66	68
clay	68	77
sand	77	117
clay	117	120
sand	120	139
clay	139	267
sand	267	271
clay	271	300
sand + clay mixed	300	321
clay	321	327
fine sand	327	342
good sand	342	367

WELL LOCATION:

sec 13 T 7 S R 9 W
2 1/4 miles N of Ocean Springs
 (distance) (direction) (nearest town)

WELL PURPOSE: Home
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 2"
- (2) total depth (feet) 367'
- (3) static water level (feet) 50' ^(below) _(above) top of ground.
- (4) casing galv. 367'
 (material) (depth)
 (size) If telescope see back.
- (5) screen 10' 357'
 (length) (depth to top)
008 stainless steel
 (size) (material)
- (6) pump 1 10
 (HP) (yield gpm)
ELECT
 (type power)
- (7) electric log NO
 (yes or no)


 (organization running log)
- (8) how well bottom plugged back
pressure valve

CODED

DRILLERS REMARKS:

If well telescopes please
sketch and show depths.

GROUND LEVEL



		*	
			E

SECTION 13

Please Indicate well location X:

ADDITIONAL INFORMATION

Lined area for additional information, consisting of approximately 18 horizontal lines.

If more than one screen,
show locations of each on sketch.