

Jackson

P238 MISSISSIPPI BOARD OF WATER COMMISSIONERS

4-30-66

WATER WELL DRILLERS LOG

Date: 49 APR 30, 1966, Driller: George Colville County Jackson

(Name)

(1) Owner of Land: Louis Harvey
(Name)
Gautier, Miss.
(Address)

(2) Location SW 1/4, SW 1/4, Sec. 8 T7R6W
3 miles W of Pascagoula
(distance) (direction) (Nearest Town)

(3) Topography: Level
(Hilly) (Flat) (Level)

(4) Purpose of Well: Dom
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials
Sand, Clay, Red Clay, Shell, etc.

Thick-
ness
Feet

Depth
Feet

<u>sand</u>	<u>6</u>	<u>6</u>
<u>clay</u>	<u>18</u>	<u>24</u>
<u>sand</u>	<u>6</u>	<u>30</u>
<u>clay</u>	<u>30</u>	<u>60</u>
<u>sand</u>	<u>48</u>	<u>108</u>
<u>clay</u>	<u>92</u>	<u>200</u>
<u>sand</u>	<u>98</u>	<u>298</u>
<u>clay</u>	<u>22</u>	<u>320</u>
<u>sand</u>	<u>3</u>	<u>323</u>
<u>clay</u>	<u>57</u>	<u>380</u>
<u>sand</u>	<u>22</u>	<u>396</u>


Information upon completion of well:

- (1) Diameter 1 1/4 inches.
- (2) Total Depth 396 feet.
- (3) Water Level 12 feet below top of ground.
- (4) Cased to 376, Size 1 1/4
- (5) Screen: Size 1/2 - 3/16, Length 10 ft.
- (6) Were any formations sealed against pollution?
no

If YES depth of formation _____

Why _____

Drillers Remarks: _____



(Use Back Side)

Well No.

Handwritten text, possibly a title or header, including the word "Journal" and other illegible characters.

Handwritten text, possibly a date or entry number, including "1877" and other illegible characters.

Handwritten text, possibly a list or notes, including "1878" and other illegible characters.

Handwritten text, possibly a list or notes, including "1879" and other illegible characters.

Handwritten text, possibly a list or notes, including "1880" and other illegible characters.