

MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY
Office of Land and Water Resources

P. O. Box 10631
Jackson, MS 39289-0631
WATER WELL DRILLERS LOG

COUNTY WELL LOCATED
JONES

WELL NUMBER **B-2024** CODED

DATE WELL COMPLETED
4-17-02

PERMIT NUMBER

NAME OF DRILLING FIRM
A-1 DRILLING SERV

LAUREL, MS

NAME & MAILING ADDRESS OF LANDOWNER
D. C. HINTON
211 SERVICE RD.
LAUREL, MS 39443

Latitude:
Longitude:

WELL LOCATION SEC TOWNSHIP RANGE
S 27 9 N 12 W

DISTANCE DIRECTION NEAREST TOWN
± 3 Miles W of LAUREL

OTHER LANDMARK

WELL PURPOSE: Home Irrigation Municipal, Industrial, Fish Pond, etc.
SPRINKLERS

PUMP DATA

PUMP TYPE (Circle One):
 Submersible Turbine Jet Flowing Well,
Other (Describe)

POWER TYPE (Circle One):
 Electric Tractor Diesel Gasoline Butane,
Other (Describe) **H/P**

DESCRIPTION OF FORMATIONS ENCOUNTERED	FROM	TO
Clay, red	0	7
Sand, red	7	14
Clay, red of white	14	27
Sand	27	31
Clay, tan	31	75
Clay, gray	75	104
Clay, gray, sandy	104	133
Sand, gray	133	139
Clay, gray	139	145
Clay w/ sand mixed	145	161
Clay, gray	161	176
Clay, sandy	176	189
Sand	189	194
Clay, gray	194	200
Sand	200	203
Clay	203	205
Sand	205	206
Clay	206	211
Rock, rock ledges, clay	211	214
Clay, gray	214	222
Clay, sandy, v. sandy	222	226

Top of Lap Pipe or Reduction in Casing

FEET IF TELESCOPED OR MORE THAN ONE SCREEN: USE BACK PAGE

WELL DATA

Well Depth **249'** Casing Diameter (In.) **4** Casing Length (Ft.) **239**

Type of Casing **PVC** Hole Depth **253'** Depth to Static Water Level **132'**

TYPE OF COMPLETION: (Circle One or More):
 Gravel Packed Underreamed Telescoped,
 (Natural Development) Open Hole Other
(Describe)


WELL GROUTED TO A DEPTH OF **17** FEET
Type Grout (circle one) Cement Bentonite, or Mix

SCREEN DATA

Diameter - Inches **4** Length - Feet **10** Slot Size - Inches **.006**

Screen Type **PVC** Depth to Bottom - Feet **248'**

I certify that the well was drilled, constructed and completed in accordance with all applicable Requirements of the Mississippi Department of Environmental Quality and/or the Mississippi Department of Health regulations and state laws.


Signature of Licensed Driller and License No. **0410**

RECEIVED
APR 22 2002
BY: OLWR **19-02**
Date

Additional Information Required On Back