

JONES

MISSISSIPPI BOARD OF WATER COMMISSIONERS

5 G 22  
7-13-60

WATER WELL DRILLERS LOG

C. T. CLARK  
WATER WELL DRILLING  
ROUTE TWO

Date: 7/13, 1960, Driller: LAUREL, MISS. County: Jones

(1) Owner of Land: W. H. Byrd  
(Name)  
Pt #4 Laurel Miss  
(Address)

(2) Location: 1/4, 1/4, Sec 18 T8 R11  
1 miles SE of LAUREL  
(distance) (direction) (Nearest Town)

(3) Topography: \_\_\_\_\_  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)


Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
0-15 Clay	15	15
15-20 Sand Clay	5	20
20-90 Mixed Clay	70	90
90-180 Mixed Sand	90	180
180-190 Clay	10	190
190-237 Sand	47	237
237-241 Clay	4	241

Information upon completion of well:

- (1) Diameter 2 inches.
- (2) Total Depth 237 feet.
- (3) Water Level 126 feet below top of ground.
- (4) Cased to 215, Size 2
- (5) Screen: Size 1/4, Length 23ft
- (6) Were any formations sealed against pollution?  
yes yes, no no.

If YES depth of formation 185 ft  
Why Fine Sand above

Drillers Remarks: It is believed low water level and 50ft drawdown due to nearness of Masonite Corp. wells



Well No.