

Lamar
 T135
 3-67
 Elec Log

MISSISSIPPI
 BOARD OF WATER COMMISSIONERS
 416 North State Street
 Jackson, Mississippi 39201

WATER WELL DRILLERS LOG

Neil Lumpkin Well Drilling Service

date well completed *Mar 22, 1967* firm name *Lamar* county well located

LANDOWNER: *Baxterville Water Assn., Inc.*
Baxterville, Miss.
 (mailing address)



WELL LOCATION:
 sec. *34* T. *2* N. R. *16* W.
Lot 28 *Blk. 3* of *BAXTERVILLE*
 (distance) miles (direction) of (nearest town)

WELL PURPOSE: *municipal*
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:
 (1) diameter (inches) *4"*
 (2) total depth (feet) *788*
 (3) static water level (feet) *260* below top of ground.
 (4) casing *metal*, *762* (material), (depth), *4"* (size) if telescope see back.
 (5) screen *20'* (length), (depth to top), *4"* (size), *metal* (material)
 (6) pump *5* (HP), *60 gal.* (yield gpm), *electric* (type power)
 (7) electric log *yes* (yes or no), *USGS* (organization running log)
 (8) how well bottom plugged *Johnson Luck pressure valve*

description of formations encountered	from	to
<i>Surface Clay</i>	<i>0</i>	<i>65</i>
<i>Sand & gravel</i>	<i>65</i>	<i>200</i>
<i>Clay</i>	<i>200</i>	<i>490</i>
<i>Sand (no good)</i>	<i>490</i>	<i>525</i>
<i>Clay</i>	<i>525</i>	<i>560</i>
<i>Sand (no good)</i>	<i>560</i>	<i>580</i>
<i>Clay</i>	<i>580</i>	<i>690</i>
<i>Sand</i>	<i>690</i>	<i>788</i>

TEST WELL

DRILLERS REMARKS:
as very good well produced plenty of water