

MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY

Office of Land and Water Resources

P.O. Box 10631
Jackson, MS 39289-0631
WATER WELL DRILLERS LOG

M191

COUNTY WELL LOCATED
Lamar
WELL NUMBER M0191 CODED
0370007-05
DATE WELL COMPLETED 9/25/2001

PERMIT NUMBER GW15846
NAME OF DRILLING FIRM GRINER DRILLING SERVICE
PO DRAWER 825
COLUMBIA, MS 39429

NAME & MAILING ADDRESS OF LANDOWNER
North Lumberton Utility Association
410 North Front Street
Lumberton, MS. 39455
Latitude:
Longitude:
WELL LOCATION SEC TOWNSHIP RANGE
3 03 1 (N) E
S 16 (W)
DISTANCE DIRECTION NEAREST TOWN
7 Miles west of Lumberton
OTHER LANDMARK
New Plant on Oil Field Road
WELL PURPOSE: Home, Irrigation, Municipal, Industrial, Fish Pond
Municipal

PUMP DATA
PUMP TYPE (Circle One):
Submersible, (Turbine,) Jet, Flowing Well,
Other (Describe)
POWER TYPE (Circle One):
(Electric,) Tractor, Diesel, Gasoline, Butane,
Other (Describe) H/P 15
DESCRIPTION OF FORMATIONS ENCOUNTERED FROM TO
sand/gravel 0 167
clay 167 324
Top of Lap Pipe or Reduction in Casing
52 FEET IF TELESCOPED OR MORE THAN ONE SCREEN: USE BACK PAGE


WELL DATA
Well Depth 162 Casing Diameter (in.) 16 Casing Length (Ft.) 112
Type of Casing steel Hole Depth 324 Depth to Static Water Level 82
TYPE OF COMPLETION: (Circle One or More):
(Gravel Packed,) (Underraamed,) Telescoped,
Natural Development, Open Hole, Other
WELL GROUTED TO A DEPTH OF 112 FEET
Type Grout (circle one): Cement, Bentonite, or (Mix)

SCREEN DATA
Diameter - inches 10 Length - Feet 40 Slot Screen - inches 0.03
Screen Type rod base Depth to Bottom - Feet 162

I certify that the well was drilled, constructed and completed in accordance with all applicable Requirements of the Mississippi Department of Environmental Quality and/or the Mississippi Department of Health regulations and state laws.
Signature of Licensed Driller and License No. Charles H. Davis, Jr. 0-581
Date 10/9/01
Addition Information Required on Back

If well telescopes please sketch and show depths.

GROUND LEVEL



If more than one screen, show location of each on sketch.


SECTION 34

Please indicate well location X.

Pump Capacity (GPM)	No. of Stages	Setting Depth	
300	7	130	FT.
PUMP TEST			
Well yielded <u>200</u> GPM with			
a drawdown of <u>48.3</u> ft.			
after <u>24</u> hours of pumping.			

**LOG DATA**

TYPE OF LOG RUN (Circle One):  No Log Run,  (Electric.)  (Gamma Ray.)  Density,  Sonic,  Neutron.  
 Other (Describe) \_\_\_\_\_

Name of Organization Running Log  
**Griner Drilling Service**

**GEOLOGIC DATA (Office Use Only)**

Surface Elev.	Geologic Unit	Unit Thickness	Depth to Top
Subs. SWL	Date	Analysis	Aquifer Test

Driller's Remarks

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_