

LAUD. MISSISSIPPI BOARD OF WATER COMMISSIONERS

A18

5-18-64

WATER WELL DRILLERS LOG

Date: 5-18, 1964, Driller: Mr Donald Hill County Lauderdale
(Name)

(1) Owner of Land: HOWARD - HAMBRICK
(Name)
COLLINSVILLE
(Address)
(2) Location: 1/4, 1/4, Sec. 35 8N 14E
T. R.
miles _____ of _____
(distance) (direction) (Nearest Town)
(3) Topography: HILLY
(Hilly) (Flat) (Level)
(4) Purpose of Well: DOMESTIC
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Sandy clay	0	23
Shale	23	45
Lignite + Sand str	45-70	
Shale	70	84
Sand m. f. shale str	84	125
Hard shale	135	165
Sandy shale str	165	175
Hard shale	175	190
Hard shale	190	220
Mudstone shale + lignite str	220	245
Hard shale	245	262
M. shale	262	280
S shale	280	330
H shale	330	345
M shale + sandy shale str	345	360
H shale	360	390
S shale + sandy shale str	390	440
M shale	440	450
F. sand	450	487
Shale	487	500


Information upon completion of well:

(1) Diameter: 4 inches.
(2) Total Depth: 500 feet.
(3) Water Level: 120 feet below top of ground.
(4) Cased to: 265, Size _____
(5) Screen: Size _____, Length _____
(6) Were any formations sealed against pollution?
_____ yes, _____ no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____



(Use Back Side)

Well No

Mail this copy to Board of Water Commissioners, 429 Miss. St. Jackson, Miss.