

LAND. MISSISSIPPI BOARD OF WATER COMMISSIONERS

N6


WATER WELL DRILLERS LOG

5

11-2-61

Date: 11. 2, 1961, Driller MCDONALD HILL County LODERDALE  
(Name)

(1) Owner of Land	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>SECURITY BUILDING CO</u> (Name)	<u>CLAY</u>	<u>0</u>	<u>12</u>
<u>45 SOUTH</u> (Address)	<u>RED SAND</u>	<u>12</u>	<u>22</u>
(2) Location: <u>29 6N 16E</u> <u>1/4</u> , <u>1/4</u> , Sec. <u>T. R.</u>	<u>ROCK</u>	<u>22</u>	<u>24</u>
<u>3</u> miles <u>SOUTH</u> , of <u>MERIDIAN</u> (distance) (direction) (Nearest Town)	<u>SAND ST CLAY</u>	<u>24</u>	<u>40</u>
(3) Topography: <u>X</u> (Hilly) (Flat) (Level)	<u>ROCK ST SHALE</u>	<u>40</u>	<u>115</u>
(4) Purpose of Well: <u>DOMESTIC</u> (Domestic Irrigation Municipal, Industrial, Other)	<u>SAND ST CLAY</u>	<u>115</u>	<u>180</u>
Information upon completion of well:	<u>SANDY SHALE</u>	<u>180</u>	<u>225</u>
(1) Diameter <u>5 3/4</u> inches.	<u>SAND</u>	<u>225</u>	<u>245</u>
(2) Total Depth <u>620'</u> feet.	<u>SHALE</u>	<u>245</u>	<u>308</u>
(3) Water Level <u>370'</u> feet below top of ground.	<u>SANDY SHALE</u>	<u>308</u>	<u>340</u>
(4) Cased to <u>463'</u> , Size <u>4"</u>	<u>SOFT SHALE</u>	<u>340</u>	<u>400</u>
(5) Screen: Size _____, Length _____	<u>SOFT SHALE</u>	<u>400</u>	<u>450</u>
(6) Were any formations sealed against pollution? _____ yes, _____ no.	<u>MED SHALE</u>	<u>450</u>	<u>510</u>
If YES depth of formation _____	<u>ROCK</u>	<u>510</u>	<u>512</u>
Why _____	<u>SHALE</u>	<u>512</u>	<u>518</u>
Drillers Remarks: _____	<u>ROCK</u>	<u>518</u>	<u>520</u>
	<u>SHALE</u>	<u>520</u>	<u>560</u>
	<u>ROCK</u>	<u>560</u>	<u>562</u>
	<u>SHALE</u>	<u>562</u>	<u>595</u>
	<u>SAND</u>	<u>595</u>	<u>620</u>



Well