

Lauderdale 3 BK 322240N0882525

TELW

P6

9-27-68

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

Date: 9-27, 1968, Driller: McDonald & Neil Inc County Lauderdale
(When well drilled) (Name) (Where well is located)


(1) Owner of Land: Clarence Ward
(Name)
RT 6 Meridian Miss
(Address)
(2) Location: NW 1/4, SE 1/4, Sec. 11 T4N R12E
10 miles East of Meridian
(distance) (direction) (Nearest Town)
(3) Topography: X
(Hilly) (Flat) (Level)
(4) Purpose of Well: home use
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
clay	20	20
shell	81	101
Rock	2	103
sandy shell	10	113
shell + lignite streaks	57	170
fine sand + shell	20	190
shell + lignite streak	10	200
fine sand	15	215
st. sand + shell	10	235
sandy shell	83	318
coarse sand	12	330

Information upon completion of well:

- (1) Diameter 2 inches.
- (2) Total Depth 330 feet.
- (3) Water Level 260 feet below top of ground.
- (4) Cased to 223, Size 2"
- (5) Screen: Size #12, Length 6'
- (6) Were any formations sealed against pollution?
X yes, no.

CODED



If YES depth of formation 81'
Why sealed off surface water
Drillers Remarks:
Yield in gpm:
Size pump:
Type power:

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.