

LAUD.
 OT7
 6-65

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

Date: _____, 19____, Driller: ROBERTS County LAUDERDALE
 (Name)

(1) Owner of Land: J. F. Parnell
 (Name)
Rt # 5
 (Address)

(2) Location: _____ 1/4, _____ 1/4, Sec. 16 T. R
10 miles E of Mend
 (distance) (direction) (Nearest Town)

(3) Topography: Hilly
 (Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
 (Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay	0	17
Sand sh + shale	17	80
Hard shale	80	110
Hard shale Lymite sh.	110	125
Sandy shale	125	130
Hard shale	130	170
Soft shale Lymite sh.	170	195
Hard + medium shale	195	225
Soft to med shale	225	247
Med-hard shale	247	265
Sandy + hard shale	265	335
Med sand str.	335	340
Soft shale sandy sh.	340	380
Sandy shale + fine sand	380	400

Information upon completion of well:

(1) Diameter 4 inches.

(2) Total Depth 400 feet.

(3) Water Level 215 feet below top of ground.

(4) Cased to 257, Size 4


(5) Screen: Size _____, Length _____

(6) Were any formations sealed against pollution?
 _____ yes, no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____



(Use Back Side)

Well No