

E-9

10-29-64

WATER WELL DRILLERS LOG

CODED

Date: OCT 29, 1964, Driller: DELTA DRILLING CO County LEFLORE

(Name)

(1) Owner of Land: B. L. EVERETT

(Name)

MONEY, MISS.

(Address)

(2) Location: 1/4, 1/4, Sec. 26 T21R1E

 miles of
(distance) (direction) (Nearest Town)

(3) Topography: (Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC
(Domestic Irrigation, Municipal, Industrial, Other)

Information upon completion of well:

- (1) Diameter 3 inches.
- (2) Total Depth 1662 feet.
- (3) Water Level FLOWS feet below top of ground.
- (4) Cased to 642, Size 3" 351', 2" 315'
- (5) Screen: Size 2, Length 20'
- (6) Were any formations sealed against pollution?
 yes, no.

If YES depth of formation

Why


Drillers Remarks: 30' LAP OF 2" IN

3" PIPE FLOWS APPROXI-

MATELY - 66 G.P.M.

| Description & Color of Materials Sand, Clay, Red Clay, Shell, etc. | Thick- ness Feet | Depth Feet |
|---|------------------------|---------------|
| GUMBO | 8 | 8 |
| SAND | 42 | 50 |
| GRAVEL | 15 | 65 |
| SAND | 14 | 79 |
| GRAVEL | 50 | 129 |
| GUMBO W/10" ROCK | 57 | 186 |
| GREEN SAND | 40 | 226 |
| SHALE W/ROCK | 24 | 250 |
| GREEN SAND | 20 | 270 |
| GUMBO | 39 | 309 |
| SHALE | 23 | 332 |
| GREEN SAND | 75 | 407 |
| SHALE | 53 | 460 |
| SAND | 46 | 506 |
| SHALE | 76 | 532 |
| GUMBO | 26 | 558 |
| SHALE | 8 | 566 |
| SAND | 35 | 601 |
| SHALE | 19 | 620 |
| SAND | 42 | 662 |

CODED



Well No.

000000