

GA

Coded


WATER WELL DRILLERS LOG

7-30-62

Date: 7-30, 1962, Driller: DELTA DRILLING - County LEFLORE

(Name)

(1) Owner of Land: <u>FOUR-FIFTHS PLANTATION</u>	Description & Color of Materials	Thick- ness Feet	Depth Feet
<u>S.E. TERRY - (Name) MANAGER -</u>	<u>SAND</u>	<u>85</u>	<u>85</u>
<u>RTE. 3, Box 71, GREENWOOD MISS (Address)</u>	<u>GRAVEL</u>	<u>61</u>	<u>146</u>
(2) Location: <u>SW 1/4, NW 1/4, Sec. 14 T22R1-W</u>	<u>SAND</u>	<u>126</u>	<u>272</u>
_____ miles _____, of _____ (distance) (direction) (Nearest Town)	<u>GUMBO</u>	<u>18</u>	<u>290</u>
(3) Topography: _____ (Hilly) (Flat) (Level)	<u>SHALE W/ 1" ROCK</u>	<u>82</u>	<u>372</u>
(4) Purpose of Well: <u>DOMESTIC</u> (Domestic Irrigation Municipal, Industrial, Other)	<u>GREEN SAND</u>	<u>119</u>	<u>491</u>
Information upon completion of well:	<u>SHALE W/ ROCKS</u>	<u>63</u>	<u>554</u>
(1) Diameter: <u>3</u> inches.	<u>GREEN SAND</u>	<u>44</u>	<u>598</u>
(2) Total Depth: <u>954</u> feet.	<u>SHALE</u>	<u>188</u>	<u>786</u>
(3) Water Level: <u>WELL FLOWS</u> feet below top of ground.	<u>GUMBO</u>	<u>20</u>	<u>816</u>
(4) Cased to: <u>954'</u> , Size: <u>3 1/2"</u>	<u>SAND</u>	<u>18</u>	<u>834</u>
(5) Screen: Size: <u>2"</u> , Length: <u>30'</u>	<u>SHALE</u>	<u>29</u>	<u>863</u>
(6) Were any formations sealed against pollution? _____ yes, _____ no.	<u>GUMBO</u>	<u>15</u>	<u>878</u>
If YES depth of formation _____	<u>SAND</u>	<u>68</u>	<u>946</u>
Why _____	<u>SHALE</u>	<u>08</u>	<u>954</u>
Drillers Remarks: <u>26' GAP OF 2" IN 3" PIPE.</u>			
<u>Elog #29 USGS</u>			



(Use Back Side)

Well No.

