

Leflore
G 101
12-10-69
USGS

CODED

1969

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

MISS. BD. OF
WATER COMM.

WATER WELL DRILLERS LOG

DEC 10 1969 DELTA DRILLING Co. LEFLORE
date well completed firm name county well located

LANDOWNER: FOUR-FIFTHS PLANTATION	description of formations encountered	from	to
M.C. (BILL) DAVIS	Sand	0	81
PT. 3, GREENWOOD, MISS (mailing address)	gravel	81	135
WELL LOCATION: N E 1/4 NE 1/4 NW 1/4	Sand	135	230
sec. 14 T. 20 N R. 1 W	gumbo	230	244
(distance) miles (direction) of (nearest town)	Sand	244	313
WELL PURPOSE: DOMESTIC (home, irrigation, municipal, industrial)	gumbo	313	373
WELL COMPLETION DATA:	Shale w/rocks	373	414
(1) diameter (inches) 4	Sand w/rocks	414	439
(2) total depth (feet) 1072	Shale w/rocks	439	453
(3) static water level (feet) FLOWS below top of ground.	Sand w/rocks	453	492
(4) casing STEEL (material), (depth) 4-3+2" if telescope see back. (size)	gumbo w/rocks	492	531
(5) screen 20 (length), (depth to top) 2, STAINLESS STEEL (size), (material)	Shale w/rocks	531	557
(6) pump 1 1/2 (HP), (yield gpm) FLEC (type power)	green sand	557	584
(7) electric log YES (yes or no)	gumbo w/rocks	584	607
(8) how well bottom plugged BACK PRESSURE VALVE	Shale	607	626
DRILLERS REMARKS: 21' LAP OF 2" IN 3" PIPE - 152' - 2" TAIL PIPE ON BOTTOM END OF WELL	gumbo	626	675
	BROWN Sand	675	720
	Shale	720	754
	Sand	754	828
	gumbo	828	858
	Sand	858	872
	Shale	872	908
	Sand	908	920
	Shale	920	962
	Sand	962	1042
	Shale	1042	1072

DEC 22 1969

MISS. BD. OF
WATER COMM.

SEE BACK.

If well telescopes please sketch and show depths.

GROUND LEVEL

100' 4" BLK
API LINE PIPE

423' 3" BLK
API LINE
PIPE

21' LAP OF
2" IN 3"


358' 2" BLK
API LINE PIPE

10' 2" SS
SCREEN

40' 2" BLK
API LINE PIPE

10' 2" BLK
API LINE PIPE

152' 2" BLK
API LINE PIPE



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.