

MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY

Office of Land and Water Resources

COUNTY WELL LOCATED Leflore	
WELL NUMBER 2060	CODED
DATE WELL COMPLETED 8-20-98	

PERMIT NUMBER
NAME OF DRILLING FIRM Irrigation Equipment Inc.
Indianola, MS

P. O. Box 10631
Jackson, MS 39289-0631
WATER WELL DRILLERS LOG

NAME & MAILING ADDRESS OF LANDOWNER Scotland Fisheries			
Rt.1, Box 170L			
Itta Bena, MS 38941			
WELL LOCATION:	SEC	TOWNSHIP	RANGE
SE/NE	4	19N	2W
		S	W
DISTANCE	DIRECTION	NEAREST TOWN	
4	NW	Itta Bena	
OTHER LANDMARK			
WELL PURPOSE: Home, Irrigation, Municipal, Industrial, Fish Pond, etc. Fish Ponds			

PUMP DATA		
PUMP TYPE (Circle One): Submersible, Turbine , Jet, Flowing Well, Other (Describe) _____		
POWER TYPE (Circle One): Electric , Tractor, Diesel, Gasoline, Butane, Other (Describe) _____ H/P 60		
Pump Capacity (GPM) 3000	No. of Stages 1	Setting Depth 80 FT.
PUMP TEST		
Well yielded _____ GPM with a drawdown of _____ ft. after _____ hours of pumping		

WELL DATA		
Well Depth 120	Casing Diameter (In.) 16	Casing Length (Ft.) 80
Type of Casing PVC	Hole Depth 120	Depth to Static Water Level 49 ft.
TYPE OF COMPLETION: (Circle One or More): Gravel Packed , Underreamed, Telescoped, Natural Development, Open Hole, Other (Describe) _____		

LOG DATA	
TYPE OF LOG RUN (Circle One): No Log Run, Electric, Gamma Ray, Density, Sonic, Neutron, Other (Describe) _____	
Name of Organization Running Log	

WELL GROUTED TO A DEPTH OF _____ FEET Type Grout (circle one): Cement, Bentonite, or Mix

GEOLOGIC DATA (Office Use Only)			
Surface Elev.	Geologic Unit	Unit Thickness	Depth to Top
Subs. SWL	Date	Analysis	Aquifer Test
Driller's Remarks			
Top of Lap Pipe or Reduction in Casing			
FEET	IF TELESCOPED OR MORE THAN ONE SCREEN: USE BACK PAGE		

SCREEN DATA		
Diameter - Inches 16	Length - Feet 40	Slot Size - Inches .050
Screen Type PVC	Depth to Bottom - Feet 120	

DESCRIPTION OF FORMATIONS ENCOUNTERED	FROM	TO
Clay	0	26
Fine Sand	26	35
Fine Sand & Gravel	35	49
Med. Sand & Gravel	49	120

FORMATIONS (Continued)	FROM	TO
RECEIVED		
NOV 12 1998		
Office of Environmental Quality Office of Land & Water Resources		

IF MORE SPACE IS NEEDED, USE BACK

If well telescopes please
sketch and show depths.


GROUND LEVEL

			X

SECTION 4

Please indicate well location X.

ADDITIONAL INFORMATION



If more than one screen,
show location of each on sketch.