


Leflore
K 18
11-8-61

CODED
WATER WELL DRILLERS LOG CODED

Date: NOV 8, 1961, Driller: DELTA DRILLING Co. County LEFLORE

(Name)

	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>JE. SIMMONS</u> (Name)	<u>GUMBO</u>	<u>42</u>	<u>42</u>
<u>ITTA BENA, MISS</u> (Address)	<u>SAND</u>	<u>51</u>	<u>93</u>
(2) Location: <u>SW 1/4, NE 1/4, Sec. 9 T19R1W</u> <u>1 3/4</u> miles <u>NE</u> of <u>ITTA BENA</u> , (distance) (direction) (Nearest Town) <u>H'WAY 82</u>	<u>GRAVEL</u>	<u>53</u>	<u>146</u>
(2) Location: <u>SW 1/4, NE 1/4, Sec. 9 T19R1W</u>	<u>COARSE SAND</u>	<u>60</u>	<u>206</u>
(2) Location: <u>SW 1/4, NE 1/4, Sec. 9 T19R1W</u>	<u>GUMBO</u>	<u>114</u>	<u>320</u>
(2) Location: <u>SW 1/4, NE 1/4, Sec. 9 T19R1W</u>	<u>SHALE</u>	<u>118</u>	<u>438</u>
(3) Topography: _____ (Hilly) (Flat) (Level)	<u>GUMBO</u> CODED	<u>127</u>	<u>565</u>
(4) Purpose of Well: <u>DOMESTIC</u> (Domestic Irrigation Municipal, Industrial, Other)	<u>SAND w/9" ROCK</u>	<u>40</u>	<u>605</u>
(4) Purpose of Well: <u>DOMESTIC</u>	<u>SHALE w/8" ROCK</u>	<u>76</u>	<u>681</u>
(4) Purpose of Well: <u>DOMESTIC</u>	<u>SAND w/6 & 3" ROCKS</u>	<u>49</u>	<u>730</u>
(4) Purpose of Well: <u>DOMESTIC</u>	<u>SHALE</u>	<u>50</u>	<u>780</u>
Information upon completion of well:	<u>SAND w/SHALE STREAKS</u>	<u>38</u>	<u>818</u>
(1) Diameter <u>3</u> inches.	<u>SAND</u>	<u>21</u>	<u>839</u>
(2) Total Depth <u>1027</u> feet.	<u>SHALE</u>	<u>13</u>	<u>852</u>
(3) Water Level <u>WELL FLOWS</u> feet below top of ground.	<u>SAND</u>	<u>38</u>	<u>890</u>
(4) Cased to <u>1027</u> , Size <u>3 X 2"</u>	<u>GUMBO</u>	<u>46</u>	<u>936</u>
(5) Screen: Size <u>2"</u> , Length <u>30</u>	<u>SAND</u>	<u>10</u>	<u>946</u>
(6) Were any formations sealed against pollution? _____yes, _____no.	<u>GUMBO</u>	<u>18</u>	<u>964</u>
If YES depth of formation _____	<u>WHITE SAND</u>	<u>53</u>	<u>1017</u>
Why _____	<u>GUMBO</u>	<u>10</u>	<u>1027</u>
Drillers Remarks: _____	CODED		



(Use Back Side)

Well No.

[The page contains extremely faint and illegible text, likely bleed-through from the reverse side of the document. The text is too light to transcribe accurately.]