

L-17
10-3-60

WATER WELL DRILLERS LOG

CODED

Date: OCT. 3, 1960, Driller: DELTA DRILLING CO. County LEFLORE

3533

(Name)

(1) Owner of Land: STANTON Co
(Name)

GREENWOOD, MISS.
(Address)

(2) Location: 1/4, 1/4, Sec. 17 T19R2E

3 miles EAST, of GREENWOOD
(distance) (direction) (Nearest Town)

(3) Topography: _____
(Hilly) (Flat) (Level)

(4) Purpose of Well: OFFICE BLDG & WAREHOUSE
(Domestic, Irrigation, Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter 3 inches.

(2) Total Depth 628 feet.

(3) Water Level _____ feet below top of ground.

(4) Cased to 628, Size 3+2"

(5) Screen: Size 2, Length 30

(6) Were any formations sealed against pollution?
_____ yes, _____ no.


If YES depth of formation _____

Why _____

Drillers Remarks: 21'-2" TAIL PIPE
ON BOTTOM OF WELL

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>TOP SOIL + SAND</u>	<u>62</u>	<u>62</u>
<u>GRAVEL</u>	<u>72</u>	<u>134</u>
<u>GUMBO</u>	<u>30</u>	<u>164</u>
<u>SANDY SHALE</u>	<u>12</u>	<u>176</u>
<u>GREEN SAND w/10" ROCK</u>	<u>22</u>	<u>198</u>
<u>SAND w/SHALE STREAKS -</u>	<u>59</u>	<u>257</u>
<u>GREEN SHALE</u>	<u>3</u>	<u>260</u>
<u>GREEN SAND w/10" ROCK</u>	<u>100</u>	<u>360</u>
<u>SHALE</u>	<u>10</u>	<u>370</u>
<u>GREEN SAND w/SHALE</u>	<u>48</u>	<u>418</u>
<u>SAND</u>	<u>29</u>	<u>447</u>
<u>SHALE</u>	<u>14</u>	<u>461</u>
<u>SAND & SHALE MIXED -</u>	<u>101</u>	<u>562</u>
<u>WHITE SAND</u>	<u>46</u>	<u>608</u>
<u>SHALE</u>	<u>20</u>	<u>628</u>

CODED



(Use Back Side)

Well No.

1934

1934